

SUPPLY OF WATER ON THE GOLD FIELDS.

Estimate for High Level.

	£	s.	d.
41,796 cubic yards of excavating, at 1s. 6d.	3,134	14	0
22 chains tunnelling, timbering, and boxing, at £70	1,540	0	0
142 chains sleepers in cuttings	73	5	0
420 chains fluming, with footway, at £40	16,800	0	0
3,171 chains boxing and supports, at £20	63,420	0	0
Nails and spikes	3,532	0	0
Footpath along the line	2,998	0	0
Clearing bush	899	10	0
Branch flumes	720	0	0
	<hr/>		
	£93,117	9	0
Contingencies, &c., 5 per cent.	4,655	0	0
	<hr/>		
	£97,772	9	0

Estimate for Low Level.

	£	s.	d.
18,872 cubic yards of excavating, at 1s. 6d.	1,415	8	0
6 chains tunnelling, timbering, and boxing, at £70	350	0	0
126 chains sleepers in cuttings	64	10	0
280 chains fluming, with footway, at £40	11,200	0	0
675½ chains boxing and supports, at £20	13,506	0	0
Nails and spikes	942	0	0
Footpath along the line	650	0	0
Clearing bush	67	0	0
	<hr/>		
	£28,194	18	0
Contingencies, &c., 5 per cent.	1,409	0	0
	<hr/>		
	£29,603	18	0

Auckland, 13th October, 1871.

JOHN JAMES O'NEILL, C.E.