



ECONOMY

is one of the principal
features of



"Poilite" Asbestos Roofing Tiles

(BRITISH MANUFACTURE)

Comparative Cost

Owing to the fact that misleading comparisons are often made of the relative cost of Roofs covered with Corrugated Iron or "Poilite" Tiles, we have obtained the following figures from a Quantity Surveyor in Dunedin. These estimates are based on Dunedin town rates for March, 1914.

Roof Construction:—26 Gauge G.C. Iron

	£	s.	d.	£	s.	d.
4in. x 2in. R.P. Rafters at 56in. centres - 62ft. super R.P. at 17/- per 100ft. ...	10	6				
5in. x 2in. R.P. Purlins at 24in. ...						
Labor per square 7/6: Cartage 6d.: Nails 5d. ...	8	5				
110ft. R.P. Sarking at 15/- per 100ft. ...	14	4				18 9
Labor, Cartage and Nails ...	5	8				
12 yards red end Sarking Felt at 4/- per yard ...	4	6				1 0 0
Labor and Clouts ...	2	5				
120lbs. G.C. Iron, 26 gauge, laid with 2 corrugations side lap and 6in. end lap ...	1	2	0			6 9
Labor and Nails ...	5	6				
						1 5 6

Cost per square for IRON Roof **£3 11 0**

If 24 gauge G.C. Iron is used instead of 26 gauge, add per square ... 10s. 6d.
If roof is painted with two coats English Oxide, add per square ... 7s. 7d.

Roof Construction:—"Poilite" Tiles

4in. x 2in. rafters at 24in. centres - 42ft. super R.P. at 17/- ...	7	2				
Labor per square 5/-: Cartage 4d.: Nails 2d. ...	5	6				
2in. x 1in. Battens, and Labor Battening and Tiling ...						12 8
"Poilite" Tiles, Clips and Nails ...						15 4
						1 14 0

Cost per square for "POILITE" Roof **£3 2 0**

For N.Z. Prices and further particulars apply to:

JOHN CHAMBERS & SON LTD.

Sole Agents for New Zealand

Fort Street (Head Office) . . . Auckland
Jervois Quay . . . Wellington
Lowe Street . . . Gisborne
200-2, St. Asaph St. . . Christchurch
Stuart and Cumberland Sts. . . Dunedin

A copy of "POILITE PICTURES" an intensely interesting illustrated Booklet of 64 pages may be had FREE for the asking.